How to connect the wide wire in the distribution box

Overview

How to Wire a Home Distribution Box In this video, we'll walk you through the process of wiring a home distribution box with a detailed connection diagram.

Key Takeaways

To connect a wide wire in a distribution box, strip the insulation to the correct length, insert it fully into the main terminal, and securely tighten the terminal screw to ensure a firm, safe connection.Step-by-Step Instructions

1. Safety First Always turn off the main power supply before working inside the distribution box to prevent electrical shock . Wear insulated gloves and use tools rated for electrical work. 2. Prepare the Wire

• Strip the insulation from the wide wire to expose the conductor, ensuring the exposed length matches the terminal requirements .

• Avoid stripping too much, which can cause short circuits, or too little, which can result in poor contact. 3. Connect to the Main Terminal

• Insert the stripped end of the wide wire into the main terminal of the distribution box, usually marked for the incoming live (phase) wire .

• Ensure the wire is fully seated so that no copper strands are exposed outside the terminal. 4. Tighten the Terminal

• Use a suitable screwdriver or wrench to tighten the terminal screw firmly, ensuring a solid mechanical and electrical connection .

© 2026 ALFA PRO COMMUNICATION SYSTEMS (Pty) Ltd - All rights reserved

• Check that the wire does not move when gently tugged. 5. Arrange and Secure Wires

• Route the wire neatly inside the box, avoiding sharp bends or contact with other components .

• Use plastic ties to bind wires together for organization and to prevent strain on the terminals . 6. Connect Branch Circuits

• After the main wire is secured, connect the outgoing circuit wires to their respective breakers or terminals according to the wiring diagram .

• Ensure each wire is correctly marked for phase, neutral, and ground. 7. Verify Connections

• Use a multimeter to check for continuity and ensure there are no short circuits .

• Confirm that all breakers and fuses are rated correctly for the connected circuits. 8. Final Safety Check

• Inspect all connections, ensure proper insulation, and verify that the box is mounted securely and ventilated .

• Only restore power after confirming that all connections are tight and safe. Following these steps ensures that the wide wire is connected securely, minimizing the risk of loose connections, overheating, or electrical faults. Proper handling and verification are crucial for both safety and reliable operation of the distribution system.

Article Content

Electric power distribution

A 50 kVA pole-mounted distribution transformer Electric power distribution is the final stage in the delivery of electricity. Electricity is

Related Video Reference

This video was associated with the source search result. Verify technical details against current product documentation and project requirements.

© 2026 ALFA PRO COMMUNICATION SYSTEMS (Pty) Ltd - All rights reserved

Contact Us

Continue your research online:

Website: https://alfa-pro.co.za
Technical inquiry: https://alfa-pro.co.za/contact.html

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

© 2026 ALFA PRO COMMUNICATION SYSTEMS (Pty) Ltd - All rights reserved