

Pre-cast concrete for distribution boxes



Overview

Distribution Boxes | Reid's Precast Cement Products Ltd
Precast cement distribution boxes endure harsh conditions, D-Boxes Our concrete D-boxes are precision.

Key Takeaways

Pre-cast concrete distribution boxes (D-boxes) are durable, customizable structures designed to evenly distribute wastewater or stormwater to drain fields or piping networks. Overview
Pre-cast concrete distribution boxes are essential components in septic systems, stormwater management, and wastewater distribution networks. They are designed to ensure uniform flow distribution, prevent clogging, and provide long-term structural stability under soil and traffic loads.

These boxes are manufactured off-site using high-strength concrete, often tested to meet ASTM standards for compressive strength and durability.

Key Features

Port Configurations: D-boxes are available with multiple outlet ports, typically ranging from 4 to 28, allowing flexibility for residential, commercial, or municipal applications.
Concrete Strength: High-quality concrete, often 5,000 psi, is used to resist corrosion, ground movement, and heavy loads.
Customization: Many manufacturers offer custom sizes, sectional construction for easier installation, and specialized applications such as fire lines, flow control, or large meter housing.

Pipe Compatibility: Pre-cast boxes can accommodate various pipe types, including Schedule 40, SDR 35, and sewer or drain pipes, often using low-pressure seals that require no mortaring.
Traffic Load Options: H-20 rated boxes are available for installation under driveways, parking lots, or other areas subject to vehicular traffic.

Benefits

Durability and Longevity: Pre-cast concrete resists corrosion, soil pressure, and environmental stress, providing a long service life. **Ease of Installation:** Pre-cast units are precision-molded and can be delivered in sections for easier handling and placement on-site. **Low Maintenance:** Once installed, these boxes require minimal maintenance while ensuring consistent flow distribution.

Versatility: Suitable for a wide range of applications, from small residential septic systems to large commercial or municipal drainage projects.

Manufacturers and Options

Cornerstone Precast: Offers 8-port and 10-port D-boxes with additional 4-port and 12-port models coming soon, emphasizing structural durability and corrosion resistance. **R. Deso, Inc.:** Provides pre-cast D-boxes and pump stations for residential, commercial, and municipal projects, focusing on long-term performance and low maintenance.

Del Zotto Products: Customizable distribution boxes for specialized applications, available in sectional construction for easier installation. **A. J.**

Foss: Offers a range of sizes from 5-outlet to 28-outlet boxes, including H-20 rated units, using high-quality concrete and Polylok low-pressure pipe seals. **Polylok, Inc.:** Supplies pre-cast distribution boxes for septic and wastewater systems internationally.

Installation Considerations

Ensure proper leveling and alignment to maintain even flow distribution. Select the appropriate port configuration based on the number of drain lines or effluent outlets. Consider traffic load requirements if the box will be installed under driveways or parking areas.

Verify local codes and regulations for septic or stormwater systems before installation. Pre-cast concrete distribution boxes provide a reliable, long-lasting solution for managing wastewater and stormwater, offering flexibility, durability, and ease of installation for a wide range of projects.

Article Content

Polylok Distribution Boxes

Polylok, Inc. is an international supplier for the precast concrete and onsite wastewater industries, producing high-grade septic tank Solution and product.

Distribution Boxes

Our team crafts each precast concrete distribution box using high-quality 5,000 psi concrete that is regularly tested using ASTM C31 and C39 quality testing guidelines.

Distribution Boxes | Wiggin Means Precast

We manufacture and stock Distributions Boxes in various sizes from 3 outlets to 14 outlets: Available in H-10 and H-20 loading Distribution Boxes accept 2", 3" and

Jefferson Concrete | PrecastBuilt to Last

Jefferson Concrete Corp. is a diversified producer of precast concrete products with a commitment to quality and value. Precastbuilt to last.

Masters Concrete | Products | Commercial Pre-Cast

Distribution Boxes Masters Commercial Precast offers several options for Distribution Boxes. Review the Additional Information section to get a complete

Distribution boxes

Patented weir opening maintains equal flow even in unlevel D-Boxes that continue to move their entire lives. Simple to install, just push into any 4" pipe, SCH. 40, SDR 35, and thin wall.

Wastewater Distribution Boxes | Jensen Infrastructure

Jensen's wastewater distribution boxes offer a comprehensive range of reliable solutions for efficient wastewater distribution in septic systems. These distribution boxes are available in various sizes to

Precast Distribution Boxes

OnSite Precast Concrete Distribution Boxes Each channel receiving wastewater flow needs to be at equal levels, or overloading will occur. Monitoring your septic's distribution box helps to ensure that

Distribution Boxes

Precast concrete distribution boxes are available in 5 sizes, small, medium, large, extra large and commercial. H-20 distribution boxes are also available.

11 Best Precast Concrete Construction Companies in

While precast concrete is an increasingly popular choice among engineers and architects because it's a more eco-friendly material than in-situ

Distribution Box Baffle

Precast distribution boxes serve to distribute the flow of wastewater from the septic tank evenly to the absorption field, leeching field or seepage pits. It is important

Electrical installation in precast concrete construction and ...

A crucial factor for maximum efficiency for concrete construction in precast concrete is the production lead times. The set-up times for reinforcement and electrical installation play a significant role here -

2"x2' Distribution Box

2"x2' Distribution Box Overview Precast distribution boxes serve to distribute the flow of wastewater from the septic tank evenly to the absorption field, leeching field or seepage pits. It is important that the

Precast Concrete Pull Boxes | Electrical Pull Boxes

Leesburg specializes in durable, versatile precast concrete pull boxes designed to meet the demands of underground electrical and utility installations.

Distribution Boxes

Concrete Distribution Box Product Code Description Dimensions Weight (lbs) DB 7 (Outlets) Hole Distribution Box 16 1/2"H x 15"W x 24"L w/ 1" drop between inlet and outlets 210 lbs Plastic

Precast Concrete Electrical Vaults, Pull Boxes, Service Boxes BC

Kon Kast manufactures precast concrete electrical utility vaults, service boxes, pull boxes, manholes, underground vaults and transformer pads for the market in the Okanagan, British Columbia,

5-Outlet Distribution Box

5-Outlet Distribution Box Overview Precast distribution boxes serve to distribute the flow of wastewater from the septic tank evenly to the absorption field, leeching

Distribution Boxes

Distribution Boxes Jefferson Concrete Corp. makes all distribution boxes with a concrete baffle at the single inlet. All the pipe penetrations have a gasket and "speed levelers" are available to ensure that

Contact Us

Continue your research online:

Website: <https://alfa-pro.co.za>

Technical inquiry: <https://alfa-pro.co.za/contact.html>

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

