What quotas need to be applied for laying optical cables



Overview

Install support structures for fiber optic cable installations before the installation of the fiber optic cable itself.

Key Takeaways

When laying optical fiber cables, key quotas include maximum pulling tension, minimum bend radius, temperature limits, and long-term load specifications to prevent damage and ensure performance.Mechanical Quotas

Pulling Tension: The cable must not be subjected to forces exceeding the manufacturer's specified maximum tensile load. For example, typical OSP loose tube or ribbon cables have a maximum pulling tension around 600 lbf, and cable breakaway devices should be used to prevent exceeding this limit during installation . Bend Radius: The minimum bend radius must be respected to avoid fiber deformation or attenuation increases. During installation, loose tube and ribbon cables typically require a bend radius of 20 times the cable diameter under tension and 10 times the diameter under static conditions . Cable Loops: When laying cable on the ground or in storage, “figure-8” loops of 2–4 meters are recommended to prevent twisting and kinking, with each loop slightly offset from the previous one . Intermediate Supports: For vertical installations, the cable weight should not exceed the long-term operating load, and intermediate attachment points are recommended to prevent sagging or overstress .

Environmental Quotas

© 2026 ALFA PRO COMMUNICATION SYSTEMS (Pty) Ltd - All rights reserved

Temperature Limits: Installation and storage temperatures must comply with the cable's data sheet specifications. LSZH sheathed cables are particularly sensitive to mechanical stress at high temperatures . Physical Hazards: The installation area should be free of sharp objects, rocks, or machinery that could damage the cable. Metallic components must be kept clear of power cables, and local building codes must be followed . Moisture Protection: Cable ends should be capped or sealed to prevent moisture ingress during installation .

Operational Quotas

Cable Handling: Swivels should be used to prevent cable twist accumulation, and pulling grips must be applied carefully to avoid jacket damage . Documentation and Planning: A thorough site survey and cable pulling plan are essential, including logistics for let-off/pulling equipment, intermediate access points, and splice locations . Load and Tension Monitoring: Residual tension after placement should remain below the maximum recommended long-term load, and clamping intervals must support the cable weight without causing movement or overstress .

Standards and References
• FOA Standard for Installing Fiber Optic Cable Plants provides comprehensive guidelines for construction, installation, and testing of fiber optic networks .

• ITU-T Recommendation L.163 outlines criteria for cable selection, route planning, tension, temperature, and handling, especially in areas with minimal infrastructure .

• Manufacturer-specific guidelines (e.g., Belden, Prysmian) provide detailed quotas for bend radius, pulling tension, and environmental conditions . By adhering to these quotas and standards, fiber optic installations can achieve optimal performance, reliability, and longevity while minimizing the risk of mechanical or environmental damage.

Article Content

The Fiber Optic Association, Inc.

Install support structures for fiber optic cable installations before the installation of the fiber optic cable itself. These structures should

© 2026 ALFA PRO COMMUNICATION SYSTEMS (Pty) Ltd - All rights reserved

Contact Us

Continue your research online:

Website: https://alfa-pro.co.za
Technical inquiry: https://alfa-pro.co.za/contact.html

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

© 2026 ALFA PRO COMMUNICATION SYSTEMS (Pty) Ltd - All rights reserved